

Task 1 – Design Project Management Key Responsibilities and Deliverables	
LHB	<ul style="list-style-type: none"> - Prepare and distribute project correspondence. - Monitor project budget. - Quality Control and Assurance. - Communication with City staff and the public.
City	<ul style="list-style-type: none"> - Project coordination, comments and review/feedback to questions and correspondence.
Deliverable(s)	<ul style="list-style-type: none"> - Project correspondence. - Well managed project.

Task 2 – Public, Historic Preservation Commission (HPC), Friends of Skyline Parkway (FSPPA), Preservation Association (DPA), Duluth Indigenous Commission (DIC) and other Interested Party Involvement and Participation

LHB believes in participatory design strategies that truly engage stakeholders. The process must be one that is shared among the diverse interests involved in the project and one that encourages stakeholders to forge a new common language as they move forward. This process, which focuses on exploration and discovery, helps stakeholders better understand their own stance, the issues they face, and the opportunities that lie ahead. It creates compelling yet appropriate solutions to tough problems and allows for a more strategic approach to implementation.

Engaged, well-informed stakeholders become supporters and advocates for projects. They produce creative ideas which become inspiring and practical solutions and strategies. They become invested in the project’s success. LHB knows how to develop this level of engagement and support and how to harness it to develop real solutions to project issues and problems. Our vast experience with this type of project also ensures we can gain the public’s confidence. The engagement process will also include assistance with engaging the Duluth Indigenous Commission and collaborating on the proposed monument that will highlight the rich history of the peak that goes well beyond the development of the parkway.

Knowing the projects goals are aligned with Section 106 requirements and the Secretary of the Interior’s Standards we do not foresee a large potential for public opposition but instead a potential for public involvement to embrace, help direct, and to celebrate the project’s ability to restore and maintain the valuable landmark. This is the very sentiment we have experienced with past public participation processes for the projects we have performed along the Parkway, and we will bring those experiences and processes to this project.

Task 2 – Public, DHPC, FSPPA, DPA and DIC Involvement and Participation Key Responsibilities and Deliverables	
LHB	<ul style="list-style-type: none"> - Facilitate and lead public meetings (1 public meeting/ open house assumed). - Prepare descriptive and graphic exhibits, drawings, renderings, and layout documents to communicate the project design goals to the public and solicit input. - Meet with/ present to the City Historic Preservation Commission to gain their feedback/ input and ensure their support for the project. - Meet with interested members from the Friends of Skyline Parkway Preservation Association and/or the Duluth Preservation Alliance to gain their feedback/ input and ensure their support for the project. - Meet with the Duluth Indigenous Commission on monument design
City	<ul style="list-style-type: none"> - Package and mail/ distribute public meeting notices. - Participate in meetings and ensure key staff are in attendance.
Deliverable(s)	<ul style="list-style-type: none"> - Graphic exhibits, drawings, renderings, and layout exhibits. - Meeting minutes and summary document of public input process. - Meeting minutes and summary documentation of meetings with City HPC, Friends of Skyline Parkway Preservation Association and the Duluth Preservation Alliance.

Task 3 – Reconnaissance, Field Surveys, and Geotechnical

The development of an accurate base map is critical for the success of any project. All our planning decisions, environmental review, permitting, and plan development will be based on this mapping.

Accurately understanding site drainage characteristics, ditching and culvert identification will be particularly important to advancing the site drainage improvements. Likewise, the presence of water in terms of its ability to soften, undermine support soils, and contribute to frost heaves can be the single largest contributor to retaining wall distress/ failure so a keen understanding of its presence within the retaining wall footprint and incorporating means to mitigate its effects will be essential.

Once we have a firm understanding of the in-place conditions and rehabilitation needs of the project LHB will engage a geotechnical subconsultant to perform a limited number of geotechnical borings. The purpose of these boring samples will be to assist us in the characterization of the retained soils which the walls support, to identify for the presence of bedrock, and potentially to assess condition at larger culvert locations. This work will be tailored to regions where the walls are noticeably experiencing distress so that we can make informed decisions regarding what is contributing to the distress and the most efficient means to rectify the situation. For purposes of our workscope estimate we have assumed 8 individual soil classification borings at an average depth of 12 feet.

Task 3 – Reconnaissance, Field Surveys, and Geotechnical Key Responsibilities and Deliverables	
LHB	<ul style="list-style-type: none"> - Detailed field reconnaissance of site by designers to ensure sound comprehensive understanding of site features and constraints. - Perform Gopher State One Call design locate to collect utility facilities information. - Review of city records for archive utility or design feature information. - Topographic field survey. - Ensure quality of culvert and utility mapping through mapping review and consultation with utility owners. - Geotechnical site investigation- 8 soil classification borings to average depth of 12 feet assumed. (LHB Subconsultant)
City	<ul style="list-style-type: none"> - Provide any existing reports, surveys, aerial photography, and access to City archive information. - Provide existing right of way information.
Deliverable(s)	<ul style="list-style-type: none"> - Mapping, including topo, underground utility mapping; right-of-way; and property ownership information. - Geotechnical report and recommendations.

Task 4 – Site Investigation, Preliminary Design, Recommendations and Cost

The initial investigation for determination of condition and rehabilitation/ reconstruction requirements is a key step in the successful delivery of this project. To support this effort, we will review archive information we have from previous work we have performed on the parkway which includes photographs dating back over 20 years. This information will help us to further understand life cycle condition for the wall elements. Determining if any portions of the wall may have originally been constructed as dry-stack stone but over time were face pointed is an item which will be of particular interest in the 106 process and for determining the historically correct rehabilitation technique. Thorough documentation of overall wall condition, regional and individual stone displacement, stone condition, presence of affecting water / groundwater features, roadway condition and ditch and culvert hydraulic assessment work will be performed to ensure a complete understanding. This will allow for well-founded preliminary recommendations and work scope cost assessment.

We will be able to utilize our previous experience and work history with similar project types to assemble sound preliminary recommendations for rehabilitation requirements for the wall, the surrounding site features (erosion, water conveyance/ runoff), the adjacent Skyline Parkway roadway, barrier stone requirements and the monument design and construction.

We understand the project’s budget is set and that an essential component of this step is to establish the extent and level of rehabilitation which most effectively utilizes the available dollars.

Task 4 – Site Investigation, Preliminary Design, Recommendations and Cost Est. Key Responsibilities and Deliverables	
LHB	<ul style="list-style-type: none"> - Review and establish project design criteria. - Perform detailed site assessment for existing conditions. - Perform preliminary assessment for rehabilitation options/ requirements. - Hydraulic analysis for ditch and culvert improvements - Prepare preliminary construction cost estimates for workscope alternatives. - Work hand in hand with City staff to determine preferred, 106 compliant rehabilitation alternative/ overall project scope.
City	<ul style="list-style-type: none"> - Provide comment and feedback throughout preliminary study.
Deliverable(s)	<ul style="list-style-type: none"> - Site assessment/ existing condition findings. - Preliminary rehabilitation recommendations and cost estimate. - Preferred rehabilitation option and estimated cost.

Task 5 – Environmental Documentation/ Rehabilitation Scoping Report/ Project Memorandum/ 106 Historic Compliance

The project environmental documentation will be completed in accordance with City, MnDOT and Federal requirements. The project will follow the MnDOT Delegated Contract Process (DCP) to ensure full compliance with federal funding requirements. To document the intended rehabilitation scope and be able to share how it will be undertaken in accordance with the SOI Standards a Rehabilitation Scoping Report will be prepared and reviewed with MnDOT CRU and the Historic Subconsultant. Following completion of this scoping report the Project Memorandum will be prepared to document and ensure environmental/ 106 and social justice compliance. Within the Project Memorandum any alternatives that were considered and the preferred alternative will be described. Potential impact areas will be reviewed and assessed. These include impacts to fish and wildlife, threatened and endangered species, visual quality, vegetation, floodplains, wetlands (not anticipated), streams and water bodies, erosion, water quality, air quality, noise, utilities, construction impacts, contaminated properties or materials, groundwater, vibration, traffic detours, access control, land use, right-of-way acquisition and relocation (not anticipated), impacts on parks and recreation lands, economic impacts, environmental justice, social impacts, and historic properties. Most notable will be the historic property requirements. Areas of controversy, if any, will also be identified. Any changes in mitigation strategies and commitments will also be documented. The required permits and approvals will be applied for and documented within the Project Memorandum. Due the projects funding sources the placement of guard stones, horizontal alignment features of Skyline Parkway and lane edge clearance zone constraints may necessitate Federal Design Exception(s) to gain approval for the Federal funding.

Within our scope we would intend to perform a cursory site assessment for the presence of wetlands. Should this assessment indicate wetlands which may be impacted are present LHB personnel would be readily available to assist the City with the performance of a wetland delineation however since it likely to not be necessary we have not included delineation services at this time.

Task 5 – Environmental Documentation/ Federal Reporting/ 106	
Key Responsibilities and Deliverables	
LHB	<ul style="list-style-type: none"> - Assessment and documentation for project environmental compliance - Prepare and apply for project permitting. - Cursory site review for presence of Wetlands which may be affected by project. - Coordination with MnDOT Cultural Resources, Project Historian (LHB Subconsultant) and State Historic Preservation Offices. - Prepare Rehabilitation Scoping Report. - Preparation of Design Exceptions. - Prepare and obtain Project Memorandum approval.
City	<ul style="list-style-type: none"> - Review application/permit forms and provide signature. - Review Project Memorandum.
Deliverable(s)	<ul style="list-style-type: none"> - Permit applications and project permits. - Complete NPDES permit application (assumption of over 1 acre disturbed). - Rehabilitation Scoping Report. - Applicable Design Exception requests. - Approved Project Memorandum.

Task 6 – Detailed Design (Plans, Specifications & Estimate)

This task includes the completion of preliminary design, final design, and preparation of the detailed construction plans and specifications. Upon establishment with the City of the approved rehabilitation concept, work will proceed to the prescribed submittal intervals. In addition, we will be sure to continually engage with the City as the design proceeds and will systematically review the project’s budget as work progresses.

Design and Plan work will proceed in accordance with City Standards, applicable AASHTO roadway and structural standards, the Secretary of the Interior’s Standards for the Treatment of Historic Properties (with plan reviews conducted by MnDOT CRU and the Historic Subconsultant), and applicable FHWA requirements. The Engineers estimate of probable construction cost will be submitted at each interval and Special Provisions will be submitted at the 60% and 90% intervals. Plan checklists, Lab Services and other DCP required forms will be submitted at 90%.

Task 6 – Detailed Design (Plans, Specifications, Estimate and DCP Forms) Key Responsibilities and Deliverables	
LHB	<ul style="list-style-type: none"> - Continually engage with City through the phases of project design on budget and rehabilitation objectives. - Perform detailed design and plan preparation. - Complete and submit 60% design plans and special provisions– complete design to the level that all significant design decisions have been addressed to properly construct the project. - Complete and submit 95% and 100% plan and special provision submittals (complete design to biddable level including quantity takeoffs, construction details, and statement of estimated quantities).
City	<ul style="list-style-type: none"> - Review and provide feedback on 60% and 90% plans. - Review and provide feedback on special provisions.
Deliverable(s)	<ul style="list-style-type: none"> - 60% and 90% Design/ Plan submittals. - 30%, 60%, 90% Engineer’s Estimate of Cost. - 95% (Tracings) Design/ Plan Submittal. - Plan checklist, right of way certificate, utility relocation certificate, and applicable DCP forms. - 100% Plan and Special Provisions Submittal- bid ready, approved by City and MnDOT. - Final Engineer’s Estimate of Cost.

Thank you again for the opportunity to assist with this work!

LHB, INC.



LISA M. KARLGAARD, PE
SENIOR STRUCTURAL ENGINEER



JOSEPH D. LITMAN, PE
CHIEF OPERATING OFFICER

Attachments: LHB Fee Estimate

c: LHB Project No. 230494

q:\23proj\230494\100 financial\proposals\bardons peak work plan letter 2023-07-20.docx

