

**A**  
**AERIAL OVERVIEW**



**B**  
**SITE OVERVIEW**





**C**  
**POLE BASE**

**LAND SITE INFORMATION:**  
 HIGHWAY ROUTE MN23  
 COUNTY: ST. LOUIS COUNTY  
 SECTION: 18N  
 TOWNSHIP: 18N  
 RANGE: 120W  
 FACILITY: REPLACEMENT 29' WOOD POLE  
 POLE TYPE: WOOD POLE  
 NO. OF CONDUCTORS: 3  
 VOLTAGE: 120/240 SINGLE PHASE  
 LIGHTING INSTALLED BY OTHERS  
 FIBER OPTIC UNDERGROUND  
 FIBER OPTIC UNDERGROUND  
 FIBER CONDUIT INSTALLED BY PROVIDER

**POWER AND FIBER ROUTING NOTE:**  
 THE PROPOSED POWER AND FIBER ROUTES ARE PRELIMINARY AND WILL BE CONFIRMED WITH THE LANDLORD AND FIBER PROVIDER PRIOR TO CONSTRUCTION. IF THE GENERAL CONTRACTOR NOTICES ANY DISCREPANCIES BETWEEN THESE PLANS AND THE ACTUAL SOURCES OF POWER AND/OR FIBER, THE PROJECT ENGINEER ASSESS TO BE NOTIFIED PRIOR TO COMMENCING WORK.

**NOTE:**  
 THE LOCATION OF EXISTING UNDERGROUND UTILITIES NEAR SITE IS PER SURVEY DATED 04/28/2018 BY WIDENH SMITH NOILING SURVEY IS (SUA) 17-8



**JACOBS**  
 Jacobs Engineering Group Inc  
 2727 Polton Road  
 Roseville, Minnesota 55113  
 www.jacobs.com

**Edge**  
 Consulting Engineers, Inc.  
 2101 Highway 134V  
 Burnsville, MN 55337  
 608.641.1249 voice  
 608.641.1549 fax  
 www.edgeconsulting.com

PROJECT NO: 20130991644  
 LOCATION CODE: 281691  
 EDGE PROJECT NO: 18936  
 CHECKED BY: OGD

REV.	DATE	DESCRIPTION	INT.
A	04/24/2018	PRELIM SMALL CELL DWGS W/VA	
B	05/15/2018	PRELIM SMALL CELL DWGS W/VA	
C	05/17/2018	PRELIM SMALL CELL DWGS KJM	
D	08/13/2018	FINAL SMALL CELL DWGS W/VA	

OTTO G. DINGELDER III  
 LICENSED PROFESSIONAL ENGINEER  
 497720  
 10/3/18

DUL SPIRIT MOUNTAIN SC11  
 DULUTH, MINNESOTA  
 REPLACEMENT LIGHT POLE  
 SMALL CELL DRAWINGS


SHEET TITLE  
**SITE PLAN**

SHEET NUMBER  
**C-101**



EXISTING POLE	29'-0" A.G.L.
POLE HEIGHT	29'-0" A.G.L.
MAXIMUM APPURTENANCE HEIGHT	34'-0" A.G.L.
PROPOSED POLE	34'-0" A.G.L.
ANTENNA TIP HEIGHT	33'-8" A.G.L.
MAXIMUM APPURTENANCE HEIGHT	34'-0" A.G.L.


NOTES:  
TYPICAL INSTALLATION SHOWN.  
ALL ELEVATIONS ARE ASSUMED TO BE MEASURED FROM ABOVE GRADE LEVEL.




NOTES:  
PROPOSED POWER AND FIBER ARE CONDUITS TO BE GROUPED TOGETHER TO MAXIMIZE AVAILABLE FREE SPACE ON POLE.  
PROPOSED POWER AND FIBER ARE CONDUIT SIZES TO BE MINIMIZED WHERE POSSIBLE.  
ALL PROPOSED JUMPER CABLES NOT IN CONDUIT TO BE PROTECTED WITH PLASTIC USGARD (SEE TO BE MINIMIZED).

**A POLE ELEVATION**

SCALE: 1" = 17'-1" = 6'-0"  
22" x 34" - 1" = 3'-0"



**B SITE ELEVATION**



NOTES:  
VERTICON TO PROVIDE FINAL RF CONFIGURATION

**C ANTENNA ORIENTATION**

SCALE: NTS

ANTENNAS					
QUANTITY	MAKE	MODEL	CENTERLINE	TIP HEIGHT	AZIMUTH
1	JMA	XTCGAP-FRO 260	32'-6" AGL	33'-8" AGL	320°

EQUIPMENT			
QUANTITY	TYPE	MAKE	MODEL
1	RRU	ERICSSON	RRUS9843
1	RRU	ERICSSON	RRUS4449
2	PSU	ERICSSON	PSU 8302
2	DIPLEXER	COMMSCOPE	CBC1923T-4310 E11F13P06

CABLING			
QUANTITY	TYPE	MAKE	MODEL
16	COAX	COMMSCOPE	IDE4-50

**D ANTENNA AND CABLING**

SCALE: NTS

**CAUTION**


Radio Frequency Fields Beyond the Point of Contact May Be Present. Do Not Touch. Do Not Stand Near. Do Not Enter. Do Not Approach. Do Not Touch. Do Not Stand Near. Do Not Enter. Do Not Approach. Do Not Touch. Do Not Stand Near. Do Not Enter. Do Not Approach.

**NOTICE**

Radio Frequency Fields Beyond the Point of Contact May Be Present. Do Not Touch. Do Not Stand Near. Do Not Enter. Do Not Approach. Do Not Touch. Do Not Stand Near. Do Not Enter. Do Not Approach.

**E RF WARNING SIGNS**

SCALE: NTS



REV.	DATE	DESCRIPTION	INT.
A	04/24/2018	PRELIM SMALL CELL DWGS (MWH)	
B	05/15/2018	PRELIM SMALL CELL DWGS (MWH)	
C	05/17/2018	PRELIM SMALL CELL DWGS (KJM)	
D	09/13/2018	FINAL SMALL CELL DWGS (MWH)	

PROJECT NO.: 20130991644  
LOCATION CODE: 281691  
EDGE PROJECT NO.: 18936  
CHECKED BY: OGD


OTTO G. DINGFELDER III  
LICENSED PROFESSIONAL ENGINEER  
49720  
STATE OF MINNESOTA  
10/13/2018

DUL SPIRIT MOUNTAIN SC1 1  
DULUTH, MINNESOTA  
REPLACEMENT LIGHT POLE  
SMALL CELL DRAWINGS


SHEET TITLE  
SITE ELEVATION

SHEET NUMBER  
T-201





**A** **UTILITY PLAN**



1. QUANTITY OF BID INDICATES CONTRACTOR BE AWARE OF ALL JOB SITE CONDITIONS AND WORK TO BE PERFORMED UNDER THIS CONTRACT.
2. CONTRACTOR SHALL PERFORM ALL VERIFICATION OBSERVATION TESTS AND EXAMINE WORK PRIOR TO THE ORDERING OF THE ELECTRICAL EQUIPMENT AND THE ACTUAL CONSTRUCTION. CONTRACTOR SHALL ISSUE A WRITTEN NOTICE OF ALL FINDINGS TO THE ARCHITECT LISTING ALL MALFUNCTIONS, FAULTY EQUIPMENT AND DISCREPANCIES.
3. HEIGHTS SHALL BE VERIFIED WITH OWNER PRIOR TO INSTALLATION.
4. THESE PLANS ARE DIAGNOSTIC ONLY. FOLLOW AS CLOSELY AS POSSIBLE.
5. EACH CONDUCTOR OF EVERY SYSTEM SHALL BE PERMANENTLY TAGGED IN EACH PANEL BOARD, PULLBOX, JUNCTION BOX, SWITCH BOX, ETC. IN COMPLIANCE WITH OCCUPATIONAL SAFETY AND HEALTH ACT (OSHA).
6. CONTRACTOR SHALL PROVIDE LABOR, MATERIALS, INSURANCE, EQUIPMENT, INSTALLATION, CONSTRUCTION TOOLS, TRANSPORTATION, ETC. FOR A COMPLETE AND PROFESSIONAL SYSTEM ENERGIZED THROUGHOUT AND AS INDICATED ON DRAWINGS. AS SPECIFIED HEREIN AND/OR AS OTHERWISE REQUIRED.
7. ALL MATERIALS AND EQUIPMENT SHALL BE NEW AND IN PERFECT CONDITION WHEN INSTALLED AND SHALL BE OF THE BEST GRADE AND OF THE SAME MANUFACTURER THROUGHOUT FOR EACH CLASS OR GROUP OF EQUIPMENT. MATERIALS SHALL BE LISTED AND APPROVED BY THE UNDERWRITER'S LABORATORY AND SHALL BEAR THE INSPECTION LABEL "I" WHERE SUBJECT TO SUCH APPROVAL. MATERIALS SHALL MEET WITH APPROVAL OF THE DIVISION OF INDUSTRIAL SAFETY AND ALL GOVERNING BODIES HAVING JURISDICTION. MATERIALS SHALL BE MANUFACTURED IN ACCORDANCE WITH APPLICABLE STANDARDS ESTABLISHED BY ANSI, NFPA, AND NETA.
8. CONTRACTOR SHALL CARRY OUT HIS WORK IN ACCORDANCE WITH ALL GOVERNING STATE, COUNTY AND LOCAL CODES AND ORDINANCES.
9. CONTRACTOR SHALL SECURE ALL NECESSARY BUILDING PERMITS.
10. COMPLETE JOB SHALL BE GUARANTEED FOR A PERIOD OF ONE (1) YEAR AFTER THE DATE OF JOB ACCEPTANCE BY OWNER. ANY WORK, MATERIAL, OR EQUIPMENT FOUND TO BE FAULTY DURING THAT PERIOD SHALL BE CORRECTED AT ONCE. UPON WRITTEN NOTIFICATION AT THE RESIDE OF THE CONTRACTOR.
11. ALL CONDUIT ONLY (CO) SHALL HAVE A PULL WIRE OR ROPE.
12. PROVIDE CONSTRUCTION ENGINEER WITH ONE SET OF COMPLETE ELECTRICAL AS INSTALLED DRAWINGS AT THE COMPLETION OF THE JOB SHOWING ACTUAL DIMENSIONS, ROUTINGS, AND CIRCUITS.
13. ALL PROCEEDURES, OPERATING MANUALS, CATALOGS, SHOP DRAWINGS, ETC. SHALL BE TURNED OVER TO OWNER AT JOB COMPLETION.
14. USE TAP CONNECTIONS ON ALL MULTIPOLARS WITH COMMON NEUTRAL CONDUCTOR.
15. ALL CONDUCTORS SHALL BE COPPER.
16. ALL CIRCUIT BREAKERS, FUSES AND ELECTRICAL EQUIPMENT SHALL HAVE AN INTERRUPTING RATING NOT LESS THAN THE MAXIMUM SHORT CIRCUIT CURRENT TO WHICH THEY MAY BE SUBJECTED AND A MINIMUM OF 1000 AIC.
17. THE ENTIRE ELECTRICAL INSTALLATION SHALL BE GROUNDED AS REQUIRED BY ALL APPLICABLE CODES AND DRAWINGS.
18. RECEPTACLES SHALL BE 20 AMPERE, 125 VOLT A.C. WHITE AS REQUIRED BY THE ARCHITECT OR APPROVED EQUAL.
19. WALL SWITCHES SHALL BE SINGLE-POLE, HUBBELL #1201 OR EQUIVALENT WHITE AS REQUIRED BY THE ARCHITECT.
20. PLASTIC PLATES FOR ALL SWITCHES, RECEPTACLES, TELEPHONE AND BLANKED OUT FETS SHALL HAVE ENGRAVED LETTERING, WHERE INDICATED ON THE DRAWINGS. WEATHERPROOF RECEPTACLES SHALL HAVE RACO R600 1/2" RANSED WORK COVERS.
21. WIRE AND CABLE CONDUCTORS SHALL BE COPPER #12 AWG MINIMUM NO BX OR ROKEX CABLE IS PERMITTED UNLESS SPECIFICALLY NOTED OTHERWISE ON DRAWINGS.
22. GROUND RODS SHALL BE AS SPECIFIED ON THE GROUNDING DRAWINGS.
23. METER SOCKET AMPERES, VOLTAGE, NUMBER OF PHASES SHALL BE AS NOTED ON THE DRAWINGS. MANUFACTURED BY SQUARE D COMPANY OR APPROVED EQUAL. IF HOST FACILITY REQUIRES THE NEW SERVICE TO BE SUBMETERED FROM THE EXISTING SERVICE SUBMETER SHALL BE OF THE I/O OR I/O-TYPE.
24. ALL MATERIALS SHALL BE UL LISTED.
25. CONDUIT:
  - A. SERVICE CONDUIT SHALL BE GRAY SCH 40 PVC BURIED MIN. 36" EXCEPT THAT SCH 40 SHALL BE USED UNDER ROADWAYS AND IN LOCATIONS SUBJECT TO CASUAL IMPACTS. JENUS SHALL BE MADE USING WIDE SWEEP (12" MIN. RADIUS) ELBOW FITTINGS. ANY GOD-SERVICED RIGID STEEL CONDUIT SHALL BE UL LABEL GALVANIZED INSIDE AND OUTSIDE. CONDUIT SHALL EXTEND MIN. 36" BELOW GRADE WITH SWEEP ELBOWS (12" R. MIN) ENDING IN PVC TRANSITION FITTINGS. RIGID CONDUIT IN CONTACT WITH EARTH SHALL BE 1/2" LAP-WRAPPED WITH HUNTS PROCESS NO. 3 EXTENDING MIN. 12" ABOVE GRADE.
  - B. INTERIOR CONDUITS SHALL BE ELECTRICAL METALLIC TUBING HAVING UL LABEL FITTINGS SHALL BE CLAMP RING COMPRESSION TYPE.
  - C. FLEXIBLE METALLIC CONDUIT SHALL HAVE UL LISTED LABEL AND MAY BE USED WHERE PERMITTED BY CODE. FITTINGS SHALL BE "JAKE" OR "SEEEZE" TYPE SEAL TIGHT FLEXIBLE CONDUIT. NO SUCH CONDUIT SHALL EXCEED SIX FEET IN LENGTH.
26. ALL ELECTRICAL EQUIPMENT SHALL BE LABELED WITH PERMANENT ENGRAVED PLASTIC LABELS.
27. PATCH, REPAIR AND PAINT ANY AREA THAT HAS BEEN DAMAGED IN THE COURSE OF THE ELECTRICAL WORK.
28. PENETRATIONS IN PRE RATED WALLS SHALL BE FIRE STOPPED IN ACCORDANCE WITH SECTION 712 PENETRATIONS - INTERNATIONAL BUILDING CODE (IBC).
29. DRILLING OR CORING HOLES IN CONCRETE WALLS OR DECKS WHETHER FOR FASTENING OR ANCHORING PURPOSES, REQUIRES "MATERIALS OR REINFORCING STEEL MUST BE SEARCHED FOR BY APPROPRIATE METHODS AND EQUIPMENT (X-RAY OR OTHER DEVICES THAT CAN ACCURATELY LOCATE "HEAT" TENDONS OR REINFORCING MUST NOT BE DRILLED, CUT OR DAMAGED UNDER ANY CIRCUMSTANCES).
30. UPON COMPLETION OF WORK, CONDUCT CONTINUITY SHORT CIRCUIT, AND FALL POTENTIAL GROUNDING TESTS FOR APPROVAL. SUBMIT TEST REPORTS TO CONSTRUCTION ENGINEER. CLEAN PREMISES OF ALL DEBRIS RESULTING FROM WORK AND LEAVE WORK IN A COMPLETE AND UNDAMAGED CONDITION.
31. CONTRACTOR TO COORDINATE WITH ULTY COMPANY FOR CONNECTION OF BOTH TEMPORARY AND PERMANENT POWER TO THE SITE. THE TEMPORARY POWER AND ALL HOOKUP COSTS TO BE PAID BY CONTRACTOR.
32. CONTRACTOR SHALL PROVIDE LABOR AND MATERIALS AS NECESSARY TO COMPLETE THE INSTALLATION OF ANY TOWER LIGHTING SYSTEM DESCRIBED IN THE 7502.

**GENERAL ELECTRICAL NOTES**



**JACOBS**  
 Jacobs Engineering Group, Inc.  
 2177 Porton Road  
 Roseville, Minnesota 55113  
 www.jacobs.com

**Edge**  
 Consulting Engineers, Inc.  
 2101 Highway 13 W  
 Burnsville, MN 55337  
 608.624.1489 voice  
 608.624.1549 fax  
 www.edgeconsult.com

PROJECT NO: 20130991644  
 LOCATION CODE: 281691  
 EDGE PROJECT NO: 18936  
 CHECKED BY: OGD

REV.	DATE	DESCRIPTION	INT.
A	04/22/2018	PRELIM SMALL CELL DWGS/W/M/H	
B	05/15/2018	PRELIM SMALL CELL DWGS/W/M/H	
C	05/17/2018	PRELIM SMALL CELL DWGS/ KJM	
D	08/13/2018	FINAL SMALL CELL DWGS W/M/H	

OTTO G. DINGFELDER  
 LICENSED PROFESSIONAL ENGINEER  
 49720  
 10/3/2018


I HEREBY CERTIFY THAT THIS PLAN SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DUL SPIRIT MOUNTAIN SC1 1  
 DULUTH, MINNESOTA  
 REPLACEMENT LIGHT POLE  
 SMALL CELL DRAWINGS

SHEET TITLE  
**UTILITY PLAN**

SHEET NUMBER  
**E-101**

NOTE:  
 TYPICAL GROUNDING PLAN DETECTED. HOWEVER DUE TO SMALL GROUNDING FOOTPRINT, 5 OHMS RESISTANCE MAY BE ENCOUNTERED. CONTRACTOR SHALL VERIFY RESISTANCE TEST AFTER COMPLETION OF CONSTRUCTION PROJECT MANAGER TO REVIEW AND APPROVE GROUND RESISTANCE RESULTS. ADDITIONAL GROUNDING IMPROVEMENTS MAY BE NECESSARY.



**A**  
**GROUNDING PLAN**



**1. SCOPE:**  
 THIS SECTION COVERS THE SPECIFICATIONS FOR CELL SITE GROUNDING. THE AREAS OF FOCUS ARE TOWER POLE BUILDING AND INSTALLATION METHODS.

**2. GENERAL:**

- 2.1 ALL GROUND RODS SHALL BE 5/8" COPPER CLAD STEEL, 10 FT LONG. GROUND RODS SHALL BE EQUALLY SPACED AT 10 FT INTERVALS PER TO SITE GROUNDING PLAN FOR DETAILS AND PLACEMENT WITH GROUNDING.
- 2.2 GROUNDING A SYSTEM SHALL BE NEGATIVELY TESTED TO ASSURE SATISFYING 5 OHMS OR LESS RESISTANCE.
- 2.3 ALL CADWELDED CONNECTIONS TO GALVANIZED MATERIAL SHALL BE PROPERLY PREPARED TO ASSURE A SATISFACTORY CADWELDED. THE CADWELDED CONNECTIONS SHALL BE COATED WITH A COULD GALVANIZING SPRAY.
- 2.4 CONTRACTORS SHALL PROVIDE PHOTO DOCUMENTATION OF THE GROUND SYSTEM BY PROVIDING A CD TO VERIZON. REQUIRED PHOTOS SHALL INCLUDE:
  - TOWER/POLE AND CABLE GROUND CONNECTIONS.
  - ALL BUS BARS AND CABLE GROUND CONNECTIONS.
  - TOWER/POLE COUNTERPOISE.
  - BUILDING COUNTERPOISE.
  - CONNECTIONS TO POWER, TELCO, A.C. FENCING (IF APPLICABLE) AND ICE BRIDGE (IF APPLICABLE).
  - CONNECTIONS TO POWER, TELCO, A.C. FENCING (IF APPLICABLE) AND ICE BRIDGE (IF APPLICABLE).
- 2.5 CONTRACTOR SHALL PROVIDE AS-BUILT PLANS SHOWING LOCATION AND DIMENSIONS OF BELOW GRADE GROUNDING FEATURES.

**3. INSTALLATION:**

- 3.1 ALL EXTERIOR ABOVE AND BELOW GROUND CONNECTIONS SHALL BE CADWELDED. NO ALUMINUM CONNECTIONS SHALL BE USED UNLESS SPECIFIED OTHERWISE ON PLANS.
- 3.2 NO RIGHT-ANGLE CADWELDED CONNECTION OTHER THAN GROUND RODS TO GROUND RING CONNECTION SHALL BE USED. ALL WIRE-TO-WIRE CONNECTIONS SHALL UTILIZE W-TYPE CONNECTIONS.
- 3.3 ALL VERTICAL JUNCTIONS SHALL NOT BE WELDED WITHIN TWO (2) FT. OF THE GROUND ROD.
- 3.4 CORNER SHIELD REQUIRED FOR ALL MECHANICAL CONNECTIONS.
- 3.5 ALL CADWELDED FINISHED WITH COLD GALVANIZED SHIELD.

**4. TOWER:**

- 4.1 A #2 SOLID BARE COPPER WIRE SHALL BE BURIED A MINIMUM FOUR (4) FT. UNDERGROUND AND ENCLOSED TOWER FOUNDATION TWO (2) FT. FROM THE FOUNDATION. THE FOUNDATION SHALL BE FINISHED TO THE TOWER GROUND RING IN TWO (2) PLACES USING CADWELDED CONNECTIONS. SUCH CONNECTIONS SHALL BE W-TYPE CADWELDED CONNECTIONS.
- 4.2 THREE (3) #2 SOLID BARE COPPER WIRES SHALL BE RUN FROM THE TOWER GROUND RING TO THE TOWER. THESE WIRES SHALL BE CONNECTED TO THE TOWER USING A CADWELDED CONNECTION. NO SHARP BENDS SHALL BE PLACED IN THESE GROUNDING LEADS.
- 4.3 GROUND SYSTEM SHALL INCLUDE THE INSTALLATION OF AN ISOLATED LIGHTNING ROD AT THE TOP OF THE TOWER ABOVE THE HIGHEST ANTENNA. A #2 INSULATED COPPER WIRE SHALL BE CONNECTED TO THE TOWER LIGHTNING ROD USING AN APPROVED MECHANICAL CONNECTOR OR CADWELDED TO TOWER STEEL.

**5. BUILDING:**

- 5.1 A #2 SOLID BARE COPPER WIRE SHALL BE BURIED A MINIMUM OF FOUR (4) FT. UNDERGROUND AND ENCLOSED BUILDING FOUNDATION TWO (2) FEET FROM THE FOUNDATION. GROUND RING CORNERS SHALL BE INSTALLED WITH A MINIMUM TWO FOOT RADIIUS (NO SHARP RIGHT ANGLE BENDS).
- 5.2 A #2 SOLID BARE COPPER WIRE SHALL BE INSTALLED FROM THE BUILDING GROUND RING AND CONNECTED TO THE COPPER BUS BAR COATED WITH MECHANICAL CONNECTION (MNC) WITHIN ONE (1) FOOT OF THE GROUND RING. A W-TYPE OR PARALLEL THE CADWELDED CONNECTIONS SHALL BE USED FOR ALL CONNECTIONS TO THE GROUND RING.
- 5.3 ONE (1) ADDITIONAL #2 SOLID BARE GROUND WIRE LEAD SHALL BE INSTALLED DIRECTLY BELOW THE ELECTRICAL SERVICE ENTRANCE PORT (GROUND LUG ON THE MAIN DISCONNECT INSIDE THE BUILDING). THIS WIRE SHALL BE CONNECTED TO THE BUILDING GROUND RING USING W-TYPE CADWELDED CONNECTION.
- 5.4 ONE (1) ADDITIONAL #2 SOLID BARE COPPER GROUND WIRE LEAD SHALL BE INSTALLED DIRECTLY BELOW EACH HVAC UNIT (IF APPLICABLE).

**A. EDE:**

- 6.1 FENCE POLES LOCATED IN GRAVEL OR GRAVEL A #2 SOLID BARE COPPER WIRE SHALL BE BURIED A MINIMUM FOUR (4) FT. UNDERGROUND AND ENCLOSED POLE FOUNDATION TWO (2) FT. FROM THE FOUNDATION. THIS GROUNDING SYSTEM SHALL BE CONNECTED TO THE POLE GROUND RING IN ONE (1) PLACE USING #2 SOLID BARE COPPER WIRE.
- 6.2 FOR POLES LOCATED IN CONCRETE OR ASPHALT A #2 SOLID BARE COPPER WIRE SHALL BE CONNECTED USING A CADWELDED TO A 5/8" COPPER CLAD STEEL 10 FT. LONG GROUND ROD. SUCH CONNECTIONS SHALL BE W-TYPE CADWELDED CONNECTIONS.
- 6.3 POLE FOUNDATION REBAR SHALL BE CONNECTED TO THE POLE GROUND RING OR GROUND ROD IN ONE (1) PLACE USING #2 SOLID BARE COPPER WIRE. SUCH CONNECTIONS SHALL BE W-TYPE CADWELDED CONNECTIONS.
- 6.4 FOR POLES CONSTRUCTED OF STEEL OR WITH STEEL BASEFLATE GROUND WIRE FROM GROUND RING OR GROUND ROD SHALL BE CONNECTED TO THE POLE USING A CADWELDED CONNECTION. NO SHARP BENDS SHALL BE PLACED IN THESE GROUNDING LEADS. SUCH CONNECTIONS SHALL BE W-TYPE CADWELDED CONNECTIONS.
- 6.5 FOR POLES CONSTRUCTED OF ALUMINUM GROUND WIRE FROM GROUND RING OR GROUND ROD SHALL BE CONNECTED TO THE POLE USING A MECHANICAL CONNECTION. NO SHARP BENDS SHALL BE PLACED IN THESE GROUNDING LEADS.

**Z. FENCING (IF APPLICABLE):**

- 7.1 A #2 SOLID BARE COPPER GROUND WIRE SHALL BE INSTALLED FROM THE FENCE CORNER POSTS TO THE GROUND RING AND SHALL BE BURIED A MINIMUM FOUR (4) FT. UNDERGROUND. THESE RUNS SHALL INCLUDE GROUND RODS EQUALLY SPACED AT 10 FT. INTERVALS. THESE RUNS SHALL BE BROUGHT ABOVE GROUND LEVEL AND SUPPORTED ABOVE GROUND WITH TEMPORARY POSTS UNTIL PERMANENT FENCING IS INSTALLED. GROUND WIRE SHALL BE CONNECTED TO THE FENCE POSTS USING CADWELDED THE CONNECTIONS.

**B. EXISTING GROUND SYSTEMS:**

- 8.1 CONTRACTOR SHALL PROVIDE CONNECTIONS TO ALL EXISTING GROUND SYSTEMS AT THE SITE (SCADA, TELEMETRY, ETC.).

**9. COMPLIANCE:**

- 9.1 ELECTRICAL CODE COMPLIANCE  
 COMPLY WITH APPLICABLE LOCAL ELECTRICAL CODES REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION AND NEC AS APPLICABLE TO ELECTRICAL GROUNDING AND BONDING PERMANENT TO SYSTEMS CIRCUITS AND EQUIPMENT.
- 9.2 UL COMPLIANCE  
 COMPLY WITH APPLICABLE REQUIREMENTS OF UL467, 488A AND 869 PERTAINING TO GROUNDING AND BONDING OF SYSTEMS CIRCUITS AND EQUIPMENT. USE GROUNDING AND BONDING PRODUCTS WHICH ARE LISTED AND LABELED FOR THEIR INTENDED USAGE.
- 9.3 IEEE COMPLIANCE  
 COMPLY WITH APPLICABLE REQUIREMENTS OF RECOMMENDED INSTALLATION PRACTICES OF IEEE STANDARDS 80, 81, 141 AND 142 PERTAINING TO GROUNDING AND BONDING OF SYSTEMS CIRCUITS AND EQUIPMENT.

**GENERAL GROUNDING NOTES**



**JACOBS**  
 Jacobs Engineering Group Inc  
 2727 Polkton Road  
 Roseville, MN 55113  
 www.jacobs.com

**Edge**  
 Consulting Engineers, Inc.  
 2101 Highway 134W  
 Burnsville, MN 55337  
 651.544.1249 voice  
 651.544.1549 fax  
 www.edgeconsult.com

PROJECT NO: 20130991644  
 LOCATION CODE: 281691  
 EDGE PROJECT NO: 18936  
 CHECKED BY: OGD

REV.	DATE	DESCRIPTION	INT.
A	04/24/2018	PRELIM SMALL CELL DWGS/WH	
B	05/15/2018	PRELIM SMALL CELL DWGS/WH	
C	05/17/2018	PRELIM SMALL CELL DWGS/WH	
D	08/13/2018	FINAL SMALL CELL DWGS/WH	

OTTO G. DINGFELDER  
 LICENSED PROFESSIONAL ENGINEER  
 49720  
 10/3/2018

DUL SPIRIT MOUNTAIN SC11  
 DULUTH, MINNESOTA  
 REPLACEMENT LIGHT POLE  
 SMALL CELL DRAWINGS

SHEET TITLE  
**GROUNDING PLAN**

SHEET NUMBER  
**E-102**